



- NOTES:
1. CONTRACTOR IS RESPONSIBLE FOR HAVING UTILITIES LOCATED IN THE FIELD.
 2. SIGN RELOCATIONS (REMOVAL, PROTECTION AND REINSTALLATIONS) ARE INCIDENTAL UNLESS OTHERWISE NOTED.
 3. CONTRACTOR SHALL LEAVE EXISTING BITUMINOUS IN PLACE ON WEST SIDE OF ROADWAY FOR DAILY ACCESS PURPOSES.
 4. CONTRACTOR SHALL MAINTAIN ACCESS TO AFFECTED RESIDENTS AT ALL TIMES.
 5. CONTRACTOR SHALL NOTIFY ALL AFFECTED RESIDENTS OF SANITARY SEWER AND WATER SERVICE WORK 24 HOURS PRIOR TO CONSTRUCTION.
 6. REMOVE EXISTING SANITARY SEWER SERVICE AND INSTALL NEW SERVICE TO +/- 5' PAST EDGE OF UNDERGROUND STORM SEWER SYSTEM CONSTRUCTION. INSULATE WITH 4" RIGID INSULATION.
 7. REMOVE EXISTING WATER SERVICE AND INSTALL NEW WATER SERVICE INCLUDING NEW CURB STOP AND BOX. WATER SERVICE DEPTH TO BE 8.0' DEEP. INSULATE WITH 4" RIGID INSULATION.
 8. CONTRACTOR SHALL REMOVE AND SALVAGE ALL MAILBOXES WITHIN CONSTRUCTION AREA. TEMPORARY MAILBOXES SHALL BE INSTALLED AT THE CORNER OF SIMPSON ST. AND LYDIA AVE. AS DIRECTED BY THE ENGINEER PRIOR TO CONSTRUCTION.
 9. RESTORE ROADWAY WITH 4" TYPE SPWEA330B WEARING COURSE IN 2 LIFTS AND 6" CLASS 5 AGGREGATE BASE.
 10. RESTORE ALL BOULEVARD AREAS WITH 4" SCREENED TOPSOIL AND HYDROMULCH.

STORM SEWER CONSTRUCTION - SIMPSON STREET
 UNDERGROUND STORM DETENTION SYSTEM

Plot Date: 03/03/2022
 Drawing Name: C:\cad\p\projects\2022\22-04_2022\PHMP Drawings\Simpson_C091.dwg
 Xrefs: X-SITE EAST, X-SITE WEST

NO.	DATE	BY	DESCRIPTION OF REVISIONS

SURVEY	RP
DRAWN	DRT
DESIGNED	DRT
CHECKED	JAF
APPROVED	JAF
CITY PROJ. NO.	22-04

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Juan Pacheco

DATE 2/21/2022 LIC. NO. 47272



160-216-024	SAP NO.
160-217-020	
160-258-001	
160-020-046	
062-651-071	

STORM SEWER SITE PLAN
 SIMPSON ST. UNDERGROUND DETENTION SYSTEM

2022 PAVEMENT MANAGEMENT PROJECT
 UTILITY AND STREET IMPROVEMENTS

SHEET NO.	
33	129
SHEET NO.	OF SHEETS